Bruhat Bangalore Mahanagara Palike
Excecutive Engineer Dasarahalli Division

Name of Work: Improvements and Ashalting to Babanna layout New vegetable Market Surrounding area roads in ward No 12, Shettyhalli Sub Division

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Civil Work								
1	KSRRB 300-1. **Earthwork excavation by manual means for roads,** drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications 10km lead= 57+2.0x1.28x10 =82.60								
	CC Drain								
	Babanna Layout								
	Chikkasandra Main Road 4th Cross	2	187.00	1.20	0.90	403.92			
	3rd Cross Road (LHS from 4th Crs)	2	63.00	1.20	0.90	136.08			
	3rd Cross Road (RHS from 4th Crs)	2	37.00	1.20	0.90	79.92			
	4th cross road(LHS from from 4th Crs)	2	64.00	1.20	0.90	138.24			
	4th cross road(RHS from 4th Crs)	1	11.00	1.20	0.90	11.88			
	5th cross road(LHS from 4th Crs)	2	64.00	1.20	0.90	138.24			
	Vigneswara Layout								
	4th Main Road	2	75.00	1.20	0.90	162.00			
	3rd Main Road	2	52.50	1.20	0.90	113.40			
	2nd Main Road	2	113.50	1.20	0.90	245.16			
	1st Main Road	2	107.00	1.20	0.90	231.12			
	Cross Road-1 from 2nd Main	1	63.50	1.20	0.90	68.58			
		1	20.00	1.20	0.90	21.60			
						1750.14	**Cum**	**220.40**	**385730.86**
2	KSRRB M2100-10. Providing and laying **Plain cement concrete of mix 1:3:6** with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222,I No-27.18)								
	CC Drain								
	Babanna Layout								
	Chikkasandra Main Road 4th Cross	2	187.00	1.20	0.15	67.32			
	3rd Cross Road (LHS from 4th Crs)	2	63.00	1.20	0.15	22.68			
	3rd Cross Road (RHS from 4th Crs)	2	37.00	1.20	0.15	13.32			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	4th cross road(LHS from from 4th Crs)	2	64.00	1.20	0.15	23.04			
	4th cross road(RHS from 4th Crs)	1	11.00	1.20	0.15	1.98			
	5th cross road(LHS from 4th Crs)	2	64.00	1.20	0.15	23.04			
	Vigneswara Layout								
	4th Main Road	2	75.00	1.20	0.15	27.00			
	3rd Main Road	2	52.50	1.20	0.15	18.90			
	2nd Main Road	2	113.50	1.20	0.15	40.86			
	1st Main Road	2	107.00	1.20	0.15	38.52			
	Cross Road-1 from 2nd Main	1	63.50	1.20	0.15	11.43			
		1	20.00	1.20	0.15	3.60			
						291.69	**Cum**	**5421.90**	**1581514.01**
3	Providing and laying plain/reinforced **cement concrete for side drains using M20 nominal mix** concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specificationsdo- Wall & bottom thickness 15cm (I No-37.59.2,P No-271)								
	CC Drain Raft								
	Babanna Layout								
	Chikkasandra Main Road 4th Cross	2	187.00	0.90	0.15	50.49			
	3rd Cross Road (LHS from 4th Crs)	2	63.00	0.90	0.15	17.01			
	3rd Cross Road (RHS from 4th Crs)	2	37.00	0.90	0.15	9.99			
	4th cross road(LHS from from 4th Crs)	2	64.00	0.90	0.15	17.28			
	4th cross road(RHS from 4th Crs)	1	11.00	0.90	0.15	1.49			
	5th cross road(LHS from 4th Crs)	2	64.00	0.90	0.15	17.28			
	Vigneswara Layout								
	4th Main Road	2	75.00	0.90	0.15	20.25			
	3rd Main Road	2	52.50	0.90	0.15	14.18			
	2nd Main Road	2	113.50	0.90	0.15	30.65			
	1st Main Road	2	107.00	0.90	0.15	28.89			
	Cross Road-1 from 2nd Main	1	63.50	0.90	0.15	8.57			
		1	20.00	0.90	0.15	2.70			
	CC Drain Wall								
	Chikkasandra Main Road 4th Cross	4	187.00	0.15	0.60	67.32			
	3rd Cross Road (LHS from 4th Crs)	4	63.00	0.15	0.60	22.68			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	3rd Cross Road (RHS from 4th Crs)	4	37.00	0.15	0.60	13.32			
	4th cross road(LHS from from 4th Crs)	4	64.00	0.15	0.60	23.04			
	4th cross road(RHS from 4th Crs)	2	11.00	0.15	0.60	1.98			
	5th cross road(LHS from 4th Crs)	4	64.00	0.15	0.60	23.04			
	Vigneswara Layout								
	4th Main Road	4	75.00	0.15	0.60	27.00			
	3rd Main Road	4	52.50	0.15	0.60	18.90			
	2nd Main Road	4	113.50	0.15	0.60	40.86			
	1st Main Road	4	107.00	0.15	0.60	38.52			
	Cross Road-1 from 2nd Main	1	63.50	0.15	0.60	5.72			
		2	20.00	0.15	0.60	3.60			
						504.74	**Cum**	**7070.20**	**3568630.42**
4	KSRB 4.9.2 : Providing **T.M.T steel reinforcement** for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specifications. Specificatio(I No-28.8.2,P No-229)								
	Consider 70kg/Cum	1	504.74	70.00		**35331.98**			
						35331.98			
						35.33	**Tn**	**72326.98**	**2555455.05**
5	Providing and Fixing **pre cast covering Slab** made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate)								
	CC Drain Raft								
	Babanna Layout								
	Chikkasandra Main Road 4th Cross	2	181.00	0.90		325.80			
	3rd Cross Road (LHS from 4th Crs)	2	63.00	0.90		113.40			
	3rd Cross Road (RHS from 4th Crs)	2	37.00	0.90		66.60			
	4th cross road(LHS from from 4th Crs)	2	64.00	0.90		115.20			
	4th cross road(RHS from 4th Crs)	1	11.00	0.90		9.90			
	5th cross road(LHS from 4th Crs)	2	64.00	0.90		115.20			
	Vigneswara Layout								
	4th Main Road	2	75.00	0.90		135.00			
	3rd Main Road	2	52.50	0.90		94.50			
	2nd Main Road	2	113.50	0.90		204.30			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	1st Main Road	2	107.00	0.90		192.60			
	Cross Road-1 from 2nd Main	1	63.50	0.90		57.15			
		1	20.00	0.90		18.00			
						1447.65	**Sqm**	**2208.00**	**3196411.20**
6	Providing and Fixing pre cast **covering Slab 250mm thick** made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge								
	Chikkasandra Main Road 4th Cross	2	5.20	1.50		15.60			
						15.60	**Sqm**	**5241.00**	**81,759.60**
7	Providing and fixing pre cast solid **cement concrete kerb stones** made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete (I No-5.30,P No-27)								
	Chikkasandra Main Road 4th Cross	2	184.00			368.00			
						368.00			
	Length /Lengthof one Kerb =Nos					**818.00**	**Nos**	**432.48**	**353768.64**
8	KSRRB 800-1. **Painting two coats after filling the surface** with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications.(I No-24.1,P No-180)								
	Chikkasandra Main Road 4th Cross	2	184.00		0.35	128.80			
						128.80	**Sqm**	**84.80**	**10,922.24**
9	KSRRB M300-14. **Excavation for roadwork in all types of soil** by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications MORTH Specificatio MORTH Specification No.301Loading and unloading with 10km lead= (I No-19.14,P No-143)								
	Babanna Layout(Widening)								
	Chikkasandra Main Road 4th Cross	2	240.00	1.75	0.375	315.00			
	3rd Cross Road (LHS from 4th Crs)	2	62.00	0.90	0.375	41.85			
	3rd Cross Road (RHS from 4th Crs)	2	37.00	0.70	0.375	19.43			
	4th cross road(LHS from from 4th Crs)	2	64.00	1.05	0.375	50.40			
	4th cross road(RHS from 4th Crs)	1	11.00	4.50	0.300	14.85			
	5th cross road(LHS from 4th Crs)	2	64.00	0.75	0.375	36.00			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	Vigneswara Layout								
	4th Main Road	2	75.00	0.90	0.375	50.63			
	3rd Main Road	2	53.00	0.85	0.375	33.79			
	2nd Main Road	2	114.00	0.95	0.375	81.23			
	1st Main Road	1	107.00	5.60	0.300	179.76			
	Cross Road-1 From 2nd Main Road	1	63.00	5.90	0.300	111.51			
	Cross Road-2 From 2nd Main Road	1	45.00	5.00	0.300	67.50			
						1001.93	**Cum**	**69.06**	**69,193.46**
10	KSRRB 300-58. **Compaction of original ground** by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications (I No-19.64,P No-147)								
	Babanna Layout(Widening)								
	4th cross road(RHS from 4th Crs)	1	11.00	4.50		49.50			
	Vigneswara Layout								
	1st Main Road	1	107.00	5.60		599.20			
	Cross Road-1 From 2nd Main Road	1	63.00	5.90		371.70			
	Cross Road-2 From 2nd Main Road	1	45.00	5.00		225.00			
						1245.40	**Sqm**	**6.36**	**7,920.74**
11	Construction of **granular sub-base Grading-V** as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications Clause 401 of MORTH V Revision.(I No-20.5,P No-153)								
	Babanna Layout(Widening)								
	Chikkasandra Main Road 4th Cross	2	240.00	1.75	0.15	126.00			
	3rd Cross Road (LHS from 4th Crs)	2	62.00	0.90	0.15	16.74			
	3rd Cross Road (RHS from 4th Crs)	2	37.00	0.70	0.15	7.77			
	4th cross road(LHS from from 4th Crs)	2	64.00	1.05	0.15	20.16			
	4th cross road(RHS from 4th Crs)	1	11.00	4.50	0.15	7.43			
	5th cross road(LHS from 4th Crs)	2	64.00	0.75	0.15	14.40			
	Vigneswara Layout								
	4th Main Road	2	75.00	0.90	0.15	20.25			
	3rd Main Road	2	53.00	0.85	0.15	13.52			
	2nd Main Road	2	114.00	0.95	0.15	32.49			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	1st Main Road	1	107.00	5.60	0.15	89.88			
	Cross Road-1 From 2nd Main Road	1	63.00	5.90	0.15	55.76			
	Cross Road-2 From 2nd Main Road	1	45.00	5.00	0.15	33.75			
						438.14	**Cum**	**1994.92**	**874044.27**
12	KSRRB M400-17. Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to **wet mix macadam** specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications(P.No-155,I No-20.18)								
	Babanna Layout(Widening)								
	Chikkasandra Main Road 4th Cross	2	240.00	1.75	0.225	189.00			
	3rd Cross Road (LHS from 4th Crs)	2	62.00	0.90	0.225	25.11			
	3rd Cross Road (RHS from 4th Crs)	2	37.00	0.70	0.225	11.66			
	4th cross road(LHS from from 4th Crs)	2	64.00	1.05	0.225	30.24			
	4th cross road(RHS from 4th Crs)	1	11.00	4.50	0.225	11.14			
	5th cross road(LHS from 4th Crs)	2	64.00	0.75	0.225	21.60			
	Vigneswara Layout								
	4th Main Road	2	75.00	0.90	0.225	30.38			
	3rd Main Road	2	53.00	0.85	0.225	20.27			
	2nd Main Road	2	114.00	0.95	0.225	48.74			
	1st Main Road	1	107.00	5.60	0.225	134.82			
	Cross Road-1 From 2nd Main Road	1	63.00	5.90	0.225	83.63			
	Cross Road-2 From 2nd Main Road	1	45.00	5.00	0.225	50.63			
						657.20	**Cum**	**2001.28**	**1315246.22**
13	KSRRB M500-6. Providing and applying **primer coat** with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications Clause 502 of MORTH V revision(P.No-158,I No-21.6)								
	Babanna Layout(Widening)								
	Chikkasandra Main Road 4th Cross	2	240.00	1.75		840.00			
	3rd Cross Road (LHS from 4th Crs)	2	62.00	0.90		111.60			
	3rd Cross Road (RHS from 4th Crs)	2	37.00	0.70		51.80			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	4th cross road(LHS from from 4th Crs)	2	64.00	1.05		134.40			
	4th cross road(RHS from 4th Crs)	1	11.00	4.50		49.50			
	5th cross road(LHS from 4th Crs)	2	64.00	0.75		96.00			
	Vigneswara Layout								
	4th Main Road	2	75.00	0.90		135.00			
	3rd Main Road	2	53.00	0.85		90.10			
	2nd Main Road	2	114.00	0.95		216.60			
	1st Main Road	1	107.00	5.60		599.20			
	Cross Road-1 From 2nd Main Road	1	63.00	5.90		371.70			
	Cross Road-2 From 2nd Main Road	1	45.00	5.00		225.00			
						2920.90	**Sqm**	**29.68**	**86,692.31**
14	KSRRB 500-7. Providing and **applying tack coat** using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM complete as per specifications (P.No-161,I No-21.7)								
	Babanna Layout								
	Chikkasandra Main Road 4th Cross	1	240.00	6.70		1608.00			
	3rd Cross Road (LHS from 4th Crs)	1	62.00	5.55		344.10			
	3rd Cross Road (RHS from 4th Crs)	1	37.00	5.55		205.35			
	4th cross road(LHS from from 4th Crs)	1	64.00	5.75		368.00			
	4th cross road(RHS from 4th Crs)	1	11.00	4.50		49.50			
	5th cross road(LHS from 4th Crs)	1	64.00	4.95		316.80			
	Vigneswara Layout					0.00			
	4th Main Road	1	75.00	5.00		375.00			
	3rd Main Road	1	53.00	6.00		318.00			
	2nd Main Road	1	114.00	6.00		684.00			
	1st Main Road	1	107.00	5.55		593.85			
	Cross Road-1 From 2nd Main Road	1	63.00	5.90		371.70			
	Cross Road-2 From 2nd Main Road	1	45.00	5.00		225.00			
						5459.30	**Sqm**	**12.72**	**69,442.30**

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
15	KSRRB M500-17. Providing and laying **dense graded bituminous macadam** using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications Clause 505 of MORTH V revisionusing 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 4.5 % VG-30 Bitumen (P.No-160,I No-21.17.6)								
	Babanna Layout(Widening)								
	Chikkasandra Main Road 4th Cross	2	240.00	1.75	0.05	42.00			
	3rd Cross Road (LHS from 4th Crs)	2	62.00	0.90	0.05	5.58			
	3rd Cross Road (RHS from 4th Crs)	2	37.00	0.70	0.05	2.59			
	4th cross road(LHS from from 4th Crs)	2	64.00	1.05	0.05	6.72			
	4th cross road(RHS from 4th Crs)	1	11.00	4.50	0.05	2.48			
	5th cross road(LHS from 4th Crs)	2	64.00	0.75	0.05	4.80			
	Vigneswara Layout								
	4th Main Road	2	75.00	0.90	0.05	6.75			
	3rd Main Road	2	53.00	0.85	0.05	4.51			
	2nd Main Road	2	114.00	0.95	0.05	10.83			
	1st Main Road	1	107.00	5.60	0.05	29.96			
	Cross Road-1 From 2nd Main Road	1	63.00	5.90	0.05	18.59			
	Cross Road-2 From 2nd Main Road	1	45.00	5.00	0.05	11.25			
						146.05	**Cum**	**6858.20**	**1001605.82**
16	KSRRB M500-19. Providing and laying **bituminous concrete** using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications Clause 507 of MORTH V revision using40/60 TPH capacity H.M.P. with Mechanical Paver Gr-II (30 mm to 45 mm) with 5.4% VG-30 Bitumen(P.No-162,I No-21.22.6)								
	Babanna Layout								
	Chikkasandra Main Road 4th Cross	1	240.00	6.70	0.04	64.32			
	3rd Cross Road (LHS from 4th Crs)	1	62.00	5.55	0.04	13.76			
	3rd Cross Road (RHS from 4th Crs)	1	37.00	5.55	0.04	8.21			
	4th cross road(LHS from from 4th Crs)	1	64.00	5.75	0.04	14.72			
	4th cross road(RHS from 4th Crs)	1	11.00	4.50	0.03	1.49			

Sl NO	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	5th cross road(LHS from 4th Crs)	1	64.00	4.95	0.04	12.67			
	Vigneswara Layout								
	4th Main Road	1	75.00	5.00	0.04	15.00			
	3rd Main Road	1	53.00	6.00	0.04	12.72			
	2nd Main Road	1	114.00	6.00	0.04	27.36			
	1st Main Road	1	107.00	5.55	0.03	17.82			
	Cross Road-1 From 2nd Main Road	1	63.00	5.90	0.03	11.15			
	Cross Road-2 From 2nd Main Road	1	45.00	5.00	0.03	6.75			
						205.97	**Cum**	**7911.84**	**1629613.55**
17	KSRRB M800-13.**Road Marking with Hot Applied Thermoplastic Compound** with Reflectrising Glass Beads on Bituminous Surface/ Concrete Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 standards specified. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification								
	Babanna Layout								
	Chikkasandra Main Road 4th Cross	2	240.00	0.10		48.00			
	3rd Cross Road (LHS from 4th Crs)	2	62.00	0.10		12.40			
	3rd Cross Road (RHS from 4th Crs)	2	37.00	0.10		7.40			
	4th cross road(LHS from from 4th Crs)	2	64.00	0.10		12.80			
	4th cross road(RHS from 4th Crs)	2	11.00	0.10		2.20			
	5th cross road(LHS from 4th Crs)	2	64.00	0.10		12.80			
	Vigneswara Layout								
	4th Main Road	2	75.00	0.10		15.00			
	3rd Main Road	2	53.00	0.10		10.60			
	2nd Main Road	2	114.00	0.10		22.80			
	1st Main Road	2	107.00	0.10		21.40			
	Cross Road-1 From 2nd Main Road	2	63.00	0.10		12.60			
	Cross Road-2 From 2nd Main Road	2	45.00	0.10		9.00			
						187.00	**Sqm**	**454.74**	**85,036.38**
								Total Construction Cost	**16872987.08**
								Towards GST 12%	**2024758.45**
								Towards KRIDL Charges4.5%	**759284.42**

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
								DPR & PMC Cost2%	337480.81
								Sub Total	19995737.74
								Utility Shifting,Miscellaneous and Rounding Off	4,262.26
								GRAND TOTAL	20000000.00

Certificate

1. The workspot was inspected and works is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike limits.
3. The rates adopted based on the PWD SR,Bangalore circle for year 2018-2019.and Data Rates

SILICON CONSULTING ENGINEERS

Assistant Engineer
Ward No-12
BBMP Bangalore

Asst. Executive Engineer,
Shettyhalli Sub Division
BBMP Bangalore

Executive Engineer,
Dasarahalli Division
BBMP Bangalore

ಪಂ.EE/AS/168/2018-19 ದಿನಾಂಕ : 20-02-2019

ರೂ.20000000=00 (Two Hundred Lakh Only)

ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ಪೂರ್ವ : ಬೆಂಗಳೂರು.

ನಂ.CE/D2/TS/196/19-20 ದಿನಾಂಕ :22/02/2019

ರೂ 200.00 Lakhs/- (Rs. Two Hundred Lakhs Only)/-

ಗಣ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ.

ತಾಂತ್ರಿಕ ಸಹಾಯಕರು

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.
ದಾಸರಹಳ್ಳಿ ಪಲಯ, ಬೆಂಗಳೂರು.